

QUOTATION	
Buyer	Quotation Ref No: CLP/Q25/03/1690rev.2
TO: Rafid Attn: Project name: Speedway Auto Spare parts Location : Ajman	Date: 24-04-2025
Lift model	Cargo Lift, 1.5 Ton capacity, wall mounted type
Parameter	
Worksite	1. Project name: without; 2. Site model: unknown; 3. Installation space size require: 4. Floors/Stops: 2; 5. Door direction: single entrance and exit; 6. Floor height from ground floor to top floor: 9100mm; 7. Pit depth: as per technical design and site conditions
Lift Parameter	1. Capacity: 1.5 Ton 2. Traveling height: 5000mm approximately 3. Stops: 2; 4. Platform dimension: 2.0 * 2.0 m 5. Platform entrance and exit: 0°;
Configuration	
Main structure	1. Lifting frame: 120* 120 rectangular steel tube; 2. Platform beam: 100* 100 square steel tube; 3. Platform floor board: 4mm thickness checkered steel board; 5. Rope: 12mm x 2; 6. Connection material: 50x50, 100x100 steel tube;
Controlling system	1. Input power: AC380V, 3P, 50HZ; 2. Main controller model: Relay Logic; 3. HOP and COP: Push Button; 4. Controlling power: 230V; 5. LED lights: without; 6. Controlling switch: limit switch;
Shaft cover material	1. Shaft structure material: 30# square steel tube; 2. Shaft surface finishes:
Door	1. Platform door: without; 2. Platform door dimension: without; 3. Landing door/ Shaft door: manual swing door; 4. Landing door size: Custom; 5. Door material: door pillar 50# square tube, door page 40# square tube; 6. Door safety sensor: Safety Switch;
Protection function	1. Emergency stop button ; 2. Door safety sensor switch; 3. Top protection limit switch;
Quantity (Set)	1.00
Unit Price (AED)	60,952.38
Gross Total (AED)	60,952.38
VAT @ 5%	3,047.62
NET TOTAL (AED)	64,000.00

Notes

Scope of works:

1. Material procurement
2. Delivery
3. Installation
4. Testing and commissioning

Other terms:

1. Scaffolding and civil works if required should provide by the client or else will be invoiced separately.
2. Client should obtain all necessary approvals and pass to complete the project.
3. Any design change or further requirements will undertake upon mutual agreement.
4. 3 phase and single-phase electricity should be provided by client.
5. Apart from elevator parts all arrangements should be done by client for site readiness.

Timeline of the Project: 30 Days

Note:

1. 3 yr warranty
2. 1yr free comprehensive service
3. 2nd and 3rd yr warranty subject to service contract with Clipston Lifts and Escalators.

Payment term:

50% advance, 20% on material delivery, and 30% after completion.